


Attachment D

Drawings

Groundwater Circulation Wells & Soil Cap Remedial Design

I:\NWPC GW RD 33754159\FINAL DESIGN\G01.dwg User: power Plotted: Mar 20, 2003 - 11:49am Last Save: Mar 20, 2003 - 11:48am

A map of the state of Oregon with a black outline. Two points in the northwestern corner are marked with asterisks (*). Two lines point from the labels 'PORTLAND' and 'CLACKAMAS' to these respective points. 'PORTLAND' is positioned slightly higher and further to the right than 'CLACKAMAS'.



S01 MONITORING WELL AND GCW SYSTEM LAYOUT (WITHOUT CAP)
S02 GCW TREATMENT SYSTEM
S03 GCW DETAILS
S04 WELL CONSTRUCTION DETAILS
S05 MONITORING WELL & GCW SYSTEM LOCATIONS (WITH CAP)
E01 UNDERGROUND POWER & TELEPHONE SITE PLAN
E02 ELECTRICAL ONE LINE DIAGRAM



EXPIRES: 6/30/04

DOCUMENT CONTROL NO. 9300.51

				JOB No. 33754167	DESIGNED: EIB	PROJ. ENGINEER: EIB	<div>URS</div> <div>111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292</div>	US EPA REGION 10	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY	DRAWING NUMBER: G01
				SCALE: NONE	DRAWN BY: JMP	APPROVED BY: TW		CAD FILE NUMBER: G01		
					CHECKED BY: EIB	DATE: MARCH 2003		SHEET: 1 OF 17		
								REV. B		
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL							
A	3/03/03	JMP	PRE-FINAL DESIGN SUBMITTAL							
No.	DATE	BY	REVISION							

I:\NWPC GW RD 33754159\FINAL DESIGN\G02.dwg User: power Plotted: Mar 19, 2003 - 11:34am Last Save: Mar 19, 2003 - 11:34am

GENERAL NOTES

GCW NOTES

- 1. STRUCTURAL, ELECTRICAL, AND MECHANICAL COMPONENTS SHALL BE DESIGNED FOR SEISMIC ZONE 3 AND IN COMPLIANCE WITH STATE AND LOCAL CODES AS APPLICABLE.
- 2. THE BUILDING FOUNDATIONS FOR FORMER PLANTS 1, 2, 3, AND 4 WERE REMOVED DURING THE PREVIOUS REMEDIAL ACTION.
- 3. TRENCH LINES ARE DIAGRAMMATIC.
- 4. THE EXISTING GROUND SURFACE IS REFERRED TO AS "EXISTING SURFACE" AND THE TOP OF THE 2 FT CAP IS REFERRED TO AS THE "FINAL SURFACE" THROUGHOUT THESE DRAWINGS.
- 5. EQUIPMENT ENCLOSURES GREATER THAN 120 SQUARE FT WILL REQUIRE A CLACKAMAS COUNTY BUILDING PERMIT.
- 6. EPA MAY CHOOSE TO ALTER THE WELL DEPTHS SHOWN ON S03 BASED ON SITE SPECIFIC CONDITIONS AS DETERMINED DURING WELL DRILLING. ACTUAL DEPTH MAY BE ± 5 FT FROM THAT SHOWN.
- 7. ALL TRENCHES THAT CROSS UNDER DRIVEWAYS OR PARKING LOTS SHALL BE BACKFILLED WITH CONTROLLED DENSITY FILL MEETING ODOT SPECIFICATION 00442.
- 8. CONTRACTOR SHALL SAW CUT ALL TRENCHES UNDER ASPHALT OR CONCRETE ON ODOT PROPERTY.
- 9. CONTRACTOR SHALL NOT INTRUDE INTO NATIVE SOILS AFTER SOIL CAP PLACEMENT.
- 10. CONTRACTOR IS RESPONSIBLE FOR INTEGRITY OF PIPES INSTALLED IN TRENCHES.
- 11. ENGINEER SHALL STAKE GCW LOCATIONS PRIOR TO SOIL CAP PLACEMENT.
- 12. SOIL REMOVED FROM TRENCHES SHALL REMAIN ONSITE. CONTRACTOR SHALL SPREAD SOIL NEXT TO TRENCH PRIOR TO SOIL CAP PLACEMENT.

SOIL CAP NOTES

- 1. SOIL CAP SHALL BE 2 FT IN THICKNESS AND SHALL FOLLOW EXISTING CONTOURS OF THE SITE, EXCEPT WHERE ALTERED ON SUB-BASE GRADING PLAN.
- 2. SOIL CAP TO BLEND INTO GRAVEL ROAD AT EDGES OF SOIL CAP.
- 3. EXISTING ONSITE PARKING LOT TO REMAIN EXCEPT AS SHOWN ON THE DEMOLITION PLAN. REMAINING PARKING LOT SHALL NOT BE CAPPED.
- 4. ONSITE ASPHALT ROADS TO REMAIN EXCEPT AS SHOWN ON DEMOLITION PLAN. SOIL CAP SHALL COVER REMAINING ONSITE ROADS.
- 5. WOODCHIP BERM IN NORTHWEST AND SOUTHWEST CORNERS OF THE SITE WILL REMAIN IN PLACE. BERM HEIGHT SHALL BE INCREASED TO BE 2 FT HIGHER THAN THE FINAL ELEVATION OF THE SOIL CAP BY NARROWING EXISTING BERM WIDTH.


- 6. CONTRACTOR SHALL FIELD VERIFY EXTENT OF WOODCHIP BERM WITH OWNER.
- 7. THE 2 FT SOIL CAP IS NOT REQUIRED ON TOP OF THE DIRT BERM. SOIL CAP SHALL BLEND INTO THE SOIL BERM ALONG THE WEST PROPERTY BOUNDARY.
- 8. CONTRACTOR SHALL NOT REMOVE SOIL BERM DURING SITE CLEARING ACTIVITIES OR USE IT AS A CAP SOIL SOURCE.
- 9. CONTRACTOR SHALL FIELD VERIFY EXTENT OF SOIL BERM WITH OWNER AFTER CLEARING ALL VEGETATION FROM BERM.
- 10. CONTRACTOR SHALL EXERT SAME COMPACTIVE EFFORT FOR SOIL CAP ALONG WOODCHIP BERM, THOUGH CONTRACTOR SHALL NOT BE HELD RESPONSIBLE FOR ATTAINING 90% COMPACTION ALONG THE SOIL CAP/WOOD BERM INTERFACE.
- 11. THE EXISTING FENCE IS TO REMAIN EXCEPT AS SHOWN ON DEMOLITION PLAN. CONTRACTOR SHALL MAKE ANY REPAIRS NECESSARY TO RESTORE FENCE TO PREVIOUS CONDITION, FOR ANY DAMAGE OCCURING DURING THIS PROJECT. REPAIRS SHALL BE AT NO COST TO OWNER.
- 12. NEW FENCE TO MATCH EXISTING.
- 13. SOIL CAP TO BE HYDROSEEDDED WITH NATIVE GRASS EROSION CONTROL MIX PER 02900.
- 14. CONTROL LOCATIONS IN WETLANDS MITIGATION AREA WILL BE SURVEYED BY ENGINEER, AT OWNERS EXPENSE, AFTER EXCAVATION AND AFTER SOIL PLACEMENT TO VERIFY ELEVATIONS AS SHOWN IN TABLE ON C02 AND C03.
- 15. FILL AREA RESULTING FROM WETLANDS EXCAVATION WILL BE SURVEYED BY ENGINEER PRIOR TO PLACEMENT OF SOIL CAP AT OWNERS EXPENSE.
- 16. SOIL CAP HAUL TRUCKS SHALL TRAVEL ONLY ON IMPORTED CAP SOIL OR ON EXISTING ASPHALT ROADS.
- 17. AT TWO FOOT DEPTH SOIL CAP VOLUME IS EQUAL TO 95,334 CUBIC YARDS IN PLACE.
- 18. WETLANDS MITIGATION AREA EXCAVATION VOLUME IS EQUAL TO 6,357 CUBIC YARDS.
- 19. AT SIX INCH DEPTH, WETLANDS MITIGATION AREA TOP SOIL VOLUME IS EQUAL TO 1,556 CUBIC YARDS.
- 20. DEMOLISHED ASPHALT SHALL BE PLACED ONSITE IN A SINGLE LAYER AS IDENTIFIED ON THE DEMOLITION PLAN.
- 21. CHIPPED VEGETATION SHALL BE PLACED ON TOP OF THE COMPLETED SOIL CAP IN WINDROWS AS IDENTIFIED ON THE FINAL GRADING PLAN.
- 22. NO VEHICLE TRAFFIC ON WELL TRENCHES IS ALLOWED PRIOR TO CAP PLACEMENT.

SYMBOLS

- EXISTING SHALLOW UPPER AQUIFER WELL (0-20 FEET BGS)
- EXISTING INTERMEDIATE UPPER AQUIFER WELL (20-60 FEET BGS)
- EXISTING LOWER UPPER AQUIFER WELL (60-110 FEET BGS)
- EXISTING LOWER AQUIFER WELL (115 FEET BGS)
- EXISTING SHALLOW UPPER AQUIFER PIEZOMETER (0-20 FEET BGS)
- EXISTING INTERMEDIATE UPPER AQUIFER PIEZOMETER (20-60 FEET BGS)
- NEW IN SITU AIR STRIPPING EQUIPMENT ENCLOSURE
- NEW IN SITU AIR STRIPPING WELL (BOTTOM AT 46 FEET BGS)
- NEW IN SITU AIR STRIPPING WELL (BOTTOM AT 66 FEET BGS)
- NEW SHALLOW UPPER AQUIFER WELL (0-20 FEET BGS)
- NEW INTERMEDIATE UPPER AQUIFER WELL (0-40 FEET BGS)
- GCW SYSTEM UNDERGROUND PIPING
- UNDERGROUND ELECTRICAL CONDUIT
- EXISTING FENCE
- NEW FENCE
- ELEVATION CONTOUR
- RAIL ROAD
- DIAMETER
- TRANSFORMER
- SERVICE METER
- CIRCUIT BREAKER
- DELTA WYE
- SWITCH
- AREA LIGHT
- TEMPORARY BENCH MARK

ABBREVIATIONS




- AMP
- BELOW GROUND SURFACE
- CIRCUIT BREAKER
- CORRUGATED METAL PIPE
- FEET
- GROUNDWATER CIRCULATION WELL
- GROUND FAULT CIRCUIT INTERRUPTER
- HIGH DENSITY POLY-ETHYLENE
- HAND, OFF, AUTO
- HIGH VOLTAGE
- INSIDE DIAMETER
- INVERT ELEVATION
- KILOVOLT AMPERE
- KILOWATT HOUR
- MOTOR
- NATIONAL ELECTRICAL MANUFACTURER'S ASSOC.
- NOT TO SCALE
- OUTER DIAMETER
- OVER LOAD
- POLE
- POLYVINYL CHLORIDE
- REFERENCE
- TO BE DETERMINED
- UNDERGROUND
- VOLT
- VARIABLE FREQUENCY DRIVE
- TRANSFORMER



EXPIRES: 6/30/04

				JOB No. 33754167	DESIGNED: EIB	PROJ. ENGINEER: EIB	URS 111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292	US EPA REGION 10 GCW & SOIL CAP REMEDIAL DESIGN	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY GENERAL NOTES, SYMBOLS, AND ABBREVIATIONS	DRAWING NUMBER: G02
				SCALE: NONE	DRAWN BY: JMP	APPROVED BY: TW				CAD FILE NUMBER: G02
					CHECKED BY: EIB	DATE: MARCH 2003				SHEET: 2 OF 17
B A	3/21/03 3/03/03	JMP JMP	FINAL DESIGN SUBMITTAL PRE-FINAL DESIGN SUBMITTAL							
No.	DATE	BY	REVISION							


I:\NWPC GW RD 33754159\FINAL DESIGN\G03.dwg User: power Plotted: Mar 19, 2003 - 11:40am Last Save: Mar 19, 2003 - 11:40am



				JOB No. 33754167	DESIGNED: EIB	PROJ. ENGINEER: EIB	<div>URS</div> <div>111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292</div>	US EPA REGION 10	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY	DRAWING NUMBER: G03	
				SCALE: AS NOTED	DRAWN BY: CAS	APPROVED BY: TW				EXISTING CONDITIONS	
					CHECKED BY: EIB	DATE: MARCH 2003				CAD FILE NUMBER: G03	
				REVISION				SHEET: 3 OF 17			
								REV. B			

B	3/21/03	JMP	FINAL DESIGN SUBMITTAL
A	3/03/03	CAS	PRE-FINAL DESIGN SUBMITTAL


I:\NWPC GW RD 33754159\FINAL DESIGN\02.dwg User: power Plotted: Mar 19, 2003 - 11:41am Last Save: Mar 19, 2003 - 11:41am



- LEGEND**
- x — x — EXISTING FENCE
 - - - - - EXISTING SITE ROADS
 - 110 - ELEVATION CONTOUR
 - ★ ELEVATION CONTROL POINT


ELEVATION CONTROL POINTS	
EASTING	NORTHING
7672205.57	645115.43
7672134.63	645088.42
7672192.62	644918.63
7672243.28	644771.89
7672313.33	644796.42

TBM #5
ELEV = 107.30'




EXPIRES: 6/30/04


				JOB No. 33754167	DESIGNED: EIB	PROJ. ENGINEER: EIB	URS 111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292	US EPA REGION 10 GCW & SOIL CAP REMEDIAL DESIGN	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY EXCAVATION & SUBBASE GRADING PLAN	DRAWING NUMBER: C02	
				SCALE: AS SHOWN	DRAWN BY: CAS	APPROVED BY: TW				CAD FILE NUMBER: C02	
					CHECKED BY: EIB	DATE: MARCH 2003				SHEET: 5 OF 17	
										REV. B	
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL								
A	3/03/03	CAS	PRE-FINAL DESIGN SUBMITTAL								
No.	DATE	BY	REVISION								



TYPICAL FENCE/CAP DETAIL 1
N.T.S. C03




TYPICAL PARKING LOT DETAIL 2
N.T.S. C03



NOTES:

1. CRUSHED ROCK TO BE 1 1/2" MINUS CRUSHED ROCK.
2. CRUSHED ROCK TO BE COMPACTED TO 95% OF ASTM 1557 (MODIFIED PROCTOR METHOD).
3. ROAD TO FOLLOW EXISTING GRADES ALONG ALIGNMENT SHOWN ON PLANS.


GRAVEL ROAD DETAIL 3
N.T.S. C03



NOTES:


1. REMOVE EXISTING BOLLARDS.
2. PLACE 2' SOIL WITHIN 5' RADIUS AND HAND COMPACT TO 90%.
3. CUT STEEL CASING TO FINAL GRADE, CUT PVC TO 4" BELOW FINAL GRADE.
4. FILL ANNULUS WITH CEMENT GROUT TO 6" BELOW TOP OF PVC.
5. WELD NEW FLUSH MOUNT MONUMENT TO STEEL CASING.
6. INSTALL 1 STEEL BOLLARD.

TYPICAL EXISTING WELL MODIFICATIONS 4
N.T.S. C03




EXPIRES: 6/30/04

				JOB No. 33754167.03000	DESIGNED: EIB	PROJ. ENGINEER: EIB	URS 111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292	US EPA REGION 10 GCW & SOIL CAP REMEDIAL DESIGN	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY SOIL CAP DETAILS	DRAWING NUMBER: C04		
				SCALE: AS NOTED	DRAWN BY: CAS	APPROVED BY: TW				CAD FILE NUMBER: C04		
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL									
A	3/3/03	JMP	PRE-FINAL DESIGN SUBMITTAL									
No.	DATE	BY	REVISION									




SOUTHEAST CORNER SECTION
N.T.S. (A C03)


NOTE:
CONTRACTOR SHALL BLEND WETLANDS EXCAVATION SPOILS TO EXISTING GRADE ALONG FENCELINE. WETLANDS EXCAVATION SPOILS SHALL BE PLACED IN A SINGLE 8" LIFT MEETING THE COMPACTION REQUIREMENTS CONTAINED IN SECTION 02300.3.3.




TYPICAL WETLAND CONSTRUCTION
N.T.S. (D C03)



SOUTH ROAD SECTION
N.T.S. (B C03)




NORTH ROAD SECTION
N.T.S. (C C03)




EXPIRES: 6/30/04

				JOB No. 33754167.03000	DESIGNED: EIB	PROJ. ENGINEER: EIB	URS 111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292	US EPA REGION 10	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY SOIL CAP SECTIONS	DRAWING NUMBER: C05		
				SCALE: AS NOTED	DRAWN BY: CAS	APPROVED BY: TW		GCW & SOIL CAP REMEDIAL DESIGN		CAD FILE NUMBER: C05		
					CHECKED BY: EIB	DATE: MARCH 2003				SHEET: 8 OF 17		
												REV. B
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL									
A	3/3/03	JMP	PRE-FINAL DESIGN SUBMITTAL									
No.	DATE	BY	REVISION									



EXPIRES: 6/30/04


				JOB No. 33754167	DESIGNED: EIB	PROJ. ENGINEER: EIB		US EPA REGION 10	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY	DRAWING NUMBER: W01						
				SCALE: AS SHOWN	DRAWN BY: CAS	APPROVED BY: TW		111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292		GCW & SOIL CAP REMEDIAL DESIGN	WETLANDS PLANTING	CAD FILE NUMBER: W01				
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL												SHEET: 10 OF 17	REV. B
A	3/03/03	CAS	PRE-FINAL DESIGN SUBMITTAL		CHECKED BY: EIB	DATE: MARCH 2003										
No.	DATE	BY	REVISION													

1. TO MINIMIZE SCALING, EQUIPMENT SHALL NOT PRODUCE APPRECIABLE HEAT INCREASE TO REINJECTED WATER.
2. THE BIOCIDES DOSING SYSTEM IS AN OPTION THAT MAY NEED TO BE ADDED AFTER SYSTEM START UP. IT IS NOT TO BE INSTALLED AS PART OF THIS SCOPE OF WORK. THE CONTRACTOR SHALL PROVIDE SUFFICIENT SPACE FOR A 55 GALLON DRUM WITHIN THE EQUIPMENT ENCLOSURE. CONTRACTOR'S PROPOSED SYSTEM CONFIGURATION SHALL ALLOW FOR FUTURE INSTALLATION OF BIOCIDES DOSING SYSTEM WITH MINIMAL SYSTEM ALTERATIONS.
3. CONTRACTOR SHALL PROVIDE BIOCIDES PIPING BETWEEN GCW AND ENCLOSURE.
4. THIS DRAWING IS DIAGRAMATIC WITH THE INTENT OF COMMUNICATING DESIRED OPERATION TO CONTRACTOR.
5. THE CONTRACTOR SHALL PROVIDE AN EQUIPMENT ENCLOSURE WITH APPROPRIATE LIGHTING AND ACCESS FOR MAINTENANCE OF EQUIPMENT. ENCLOSURE SHALL HAVE AT LEAST ONE STANDARD 110-V OUTLET.
6. THE CONTRACTOR MAY COMBINE COMPONENTS FOR SYSTEMS CONTAINED IN THE SAME EQUIPMENT ENCLOSURE SUCH THAT THE INTENDED OPERATION FOR EACH GCW IS MAINTAINED.
7. EQUIPMENT ENCLOSURES GREATER THAN 120 SQUARE FT WILL REQUIRE A CLACKAMAS COUNTY BUILDING PERMIT.
8. SAMPLE PORT LOCATIONS NOT SHOWN ON DRAWING ARE DESCRIBED IN SPECIFICATION SECTION 15101.2.4.
9. PRESSURE TEST POINT LOCATIONS NOT SHOWN ON DRAWING ARE DESCRIBED IN SPECIFICATION SECTION 15101.2.5.
10. PACKER SHALL HAVE INFLATION LINE WHICH WILL REMAIN IN WELL VAULT.
11. PACKER SHALL HAVE A GAS RELIEF LINE TO VENT AWAY GAS BUILD-UP BELOW THE PACKER. LINE WILL BE NORMALLY CLOSED WITH VALVE IN WELL VAULT.
12. CARBON AND ZEOLITE PER SPECIFICATION SECTION 11201.




EXPIRES: 6/30/04

				JOB No. 33754167.03000		DESIGNED: EIB		PROJ. ENGINEER: EIB		<div>URS</div> <div>111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292</div>		US EPA REGION 10		NORTHWEST PIPE & CASING / HALL PROCESS COMPANY		DRAWING NUMBER: S02			
				SCALE: AS NOTED		DRAWN BY: JMP		APPROVED BY: TW						GCW TREATMENT SYSTEM		CAD FILE NUMBER: S02			
B 3/21/03 JMP FINAL DESIGN SUBMITTAL																			
A 1/27/03 JMP PRE-FINAL DESIGN SUBMITTAL																			
No.		DATE		BY		REVISION		CHECKED BY: EIB		DATE: MARCH 2003		GCW & SOIL CAP REMEDIAL DESIGN		GCW TREATMENT SYSTEM		SHEET: 12 of 17		REV. B	




TYPICAL WELL TRENCH
N.T.S.

1
S01



TYPICAL ODOT WELL TRENCH
N.T.S.

2
S01




TYPICAL ELECTRICAL CONDUIT TRENCH
N.T.S.

3
E01


NOTES:

1. ALL HDPE PIPE SHALL BE SLOPED TO DRAIN TO THE GCW WELLS.
2. ALL TRENCHES THAT CROSS UNDER DRIVEWAYS OR PARKING LOTS SHALL BE BACKFILLED WITH CONTROLLED DENSITY FILL MEETING ODOT SPECIFICATION 00442. THESE LOCATIONS SHALL BE RETURNED TO PRE-EXISTING CONDITIONS.
3. A PAD SHALL BE INSTALLED IN ANY GCW OR MONITORING WELL LOCATIONS WHERE THE 2" SOIL CAP HAS NOT BEEN PLACED. THE CONTRACTOR SHALL PROTECT WELLS BY PLACING A 10' DIAMETER SOIL PAD THAT IS 2' DEEP AND COMPACTED TO 90%.



GCW PAD DETAIL
N.T.S.

4
-




EXPIRES: 6/30/04

				JOB No. 33754167.03000	DESIGNED: EIB	PROJ. ENGINEER: EIB	URS 111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292	US EPA REGION 10	NORTHWEST PIPE & CASING / HALL PROCESS COMPANY GCW DETAILS	DRAWING NUMBER: S03		
				SCALE: AS NOTED	DRAWN BY: JMP	APPROVED BY: TW				CAD FILE NUMBER: S03		
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL									
A	1/27/03	JMP	PRE-FINAL DESIGN SUBMITTAL									
No.	DATE	BY	REVISION									
					CHECKED BY: EIB	DATE: MARCH 2003					SHEET: 13 of 17	REV. B



1. ONE LINE DIAGRAM IS TYPICAL FOR A SINGLE GCW SYSTEM. CONTRACTOR MAY ELECT TO COMBINE THE CONTROL PANELS FOR MULTIPLE SYSTEMS IN THE SAME EQUIPMENT ENCLOSURE, BUT SHALL ALSO SUBMIT DETAILS FOR ANY PROPOSED CHANGES.
2. FOR ILLUSTRATIVE PURPOSES ONLY, CONTRACTOR TO COMPLETE ELECTRICAL DESIGN. FOR GCW SEQUENCE OF OPERATION DESCRIPTION SEE SPECIFICATION SECTION 11201.

SHEET:	REV.
17 OF 17	B

				JOB No. 33754167.03000	DESIGNED: TK	PROJ. ENGINEER: EIB		US EPA REGION 10	NORTHWEST PIPE & CASING/HALL PROCESS COMPANY	DRAWING NUMBER: E02	
				SCALE: AS NOTED	DRAWN BY: BJR	APPROVED BY: TW				CAD FILE NUMBER: E02	
					CHECKED BY: TK	DATE: MARCH 2003				SHEET: 17 OF 17	
										REV. B	
B	3/21/03	JMP	FINAL DESIGN SUBMITTAL								
A	1/27/03	JMP	PRE-FINAL DESIGN SUBMITTAL								
No.	DATE	BY	REVISION								
				111 S.W. Columbia, Suite 900 Portland, Oregon 97201 (tel) 503-222-7200 (fax) 503-222-4292							
				GCW & SOIL CAP REMEDIAL DESIGN							
				ELECTRICAL ONE LINE DIAGRAM							